



REF A:
KIRIUM PRO 1, DIRECT POST, 16x300mA 3K LED ARRAY, A2 OPTIC, RAL5005 BLACK FINISH, 35 LUX PHOTOCELL

REF B:
KIRIUM 200, 300mA 3K LED ARRAY, ASYMMETRIC WIDE OPTIC, RAL5005 BLACK FINISH

REF C:
KIRIUM WALL, 16x300mA 3K LED ARRAY, CLEAR WIDE, RAL5005 BLACK FINISH

LUMINAIRE SCHEDULE						
SYMBOL	REF	CONFIGURATION	DESCRIPTION	LUMENS	S/P RATIO	CUT-OFF CLASS
••	A	SINGLE	KIRIUM PRO1, DIRECT POST, 3K LED ARRAY, A2 OPTIC, 6m TLS	2065	1.20	FULL CUT-OFF
•	B	SINGLE	KIRIUM 200, 3K LED ARRAY, ASYMMETRIC WIDE OPTIC, 1m TLS	854	1.20	NON CUT-OFF
•	C	SINGLE	KIRIUM WALL, 3K LED ARRAY, CLEAR WIDE, 3m TLS	1677	1.20	NON CUT-OFF

Calculation Summary									
Grid Ref	Measurement	Units	Eav	E _{max}	E _{min}	U ₀	U _d	X Pitch	Y Pitch
Apartment Parking 15	illuminance	Lux	3.94	23.4	0.1	0.03	0.00	1.5	1.5
Apartment Parking 29	illuminance	Lux	5.90	22.7	0.3	0.05	0.01	1.5	1.5
Apartment Parking 41	illuminance	Lux	5.83	25.3	0.1	0.02	0.00	1.5	1.5
Area 01	illuminance	Lux	7.82	59.2	0.1	0.01	0.00	1.5	1.5
Area 02	illuminance	Lux	5.82	53.2	0.1	0.02	0.00	1.5	1.5
Area 03	illuminance	Lux	5.44	49.8	0.0	0.00	0.00	1.5	1.5
Area 04	illuminance	Lux	8.19	53.8	0.3	0.04	0.01	1.5	1.5
Area 05	illuminance	Lux	5.70	49.0	0.2	0.04	0.00	1.5	1.5
Area 06	illuminance	Lux	6.29	59.3	0.1	0.02	0.00	1.5	1.5
Area 07	illuminance	Lux	6.27	54.9	0.1	0.02	0.00	1.5	1.5
Area 8	illuminance	Lux	3.65	55.0	0.0	0.00	0.00	1.5	1.5
Road 01	illuminance	Lux	5.45	14.5	0.9	0.17	0.06	1.5	1.5
Road 02	illuminance	Lux	4.41	14.6	0.9	0.20	0.06	1.5	1.5
Road 03	illuminance	Lux	4.91	14.6	0.9	0.18	0.06	1.5	1.5
Road 04	illuminance	Lux	4.78	14.4	0.8	0.17	0.06	1.5	1.5



CONSTRUCTION (DESIGN AND MANAGEMENT) REGULATIONS 2015 DESIGNERS RISK INFORMATION

IN ACCORDANCE WITH THE CONSTRUCTION (DESIGN AND MANAGEMENT) REGULATIONS THE HAZARDS AND RISKS ASSOCIATED WITH CONSTRUCTING, MAINTAINING AND CLEARING THE STRUCTURE HAVE BEEN ASSESSED. THE DESIGN SOLUTION HAS MITIGATED THESE WHERE POSSIBLE. HOWEVER, RESIDUAL UNUSUAL HAZARDS OR RISKS IDENTIFIED HAVE BEEN RECORDED IN THE DESIGNERS RISK INFORMATION SPECIFIC TO THE PROJECT. ASSUMPTIONS MADE ABOUT THE METHOD OF CONSTRUCTION, MAINTENANCE AND DEMOLITION HAVE BEEN STATED WHERE THESE FORM AN INTEGRAL PART OF MANAGING THE RISKS AND HAZARDS. HOWEVER, THIS DOES NOT RESTRICT THE CONTRACTOR TO THESE METHODS ALONE. IT IS UNDERSTOOD THAT A COMPETENT CONTRACTOR WILL CARRY OUT CONSTRUCTION, MAINTENANCE AND DEMOLITION WORK IN ACCORDANCE WITH RECOGNISED GOOD INDUSTRY PRACTICE. THE ABOVE NOTES REFER SPECIFICALLY TO THE INFORMATION SHOWN ON THIS DRAWING AS DESIGNERS. PLEASE REFER TO THE DESIGNERS RISK INFORMATION FOR FURTHER CLARIFICATION AND THOSE RELEVANT TO OTHER DISCIPLINES.

THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEERS', ARCHITECTS' AND SPECIALISTS' DRAWINGS AND THE SPECIFICATION.

DESIGN INFORMATION FROM OTHER DISCIPLINES SHOWN ON THIS DRAWING IS FOR COORDINATION PURPOSES ONLY.

DO NOT SCALE FROM THIS DRAWING MANUALLY OR ELECTRONICALLY. WRITTEN PERMISSION MUST BE OBTAINED FROM MLM PRIOR TO SCALING ELECTRONICALLY OR USING THIS ELECTRONIC FILE.

ALL DIMENSIONS IN MILLIMETRES UNLESS OTHERWISE STATED.

BS EN REQUIREMENTS FOR PEDESTRIANS & PEDAL CYCLISTS TABLE 3 - P LIGHTING CLASSES

CLASS P4 (1.2 SP RATIO):
4.0-6.0 LX EAV
0.8 LUX EMIN

BS EN 13201-2:2015
6.1 Requirements for pedestrians & pedal cyclists
Table 3 - P Lighting Classes

Class P4
5.0 - 7.5lx Eav
1.0lx Emin

PO3	13.03.2020	STAGE 2 ISSUE	LAA	JCG	BS
PO2	26.02.2020	STAGE 2 ISSUE	ICG	JCG	BS
PO1	05.09.2019	STAGE 2 ISSUE	PG	JAC	BS
REV	DATE	REVISION	MADE	CHK	APP

STAGE 2

STATUS: S2 SUITABLE FOR INFORMATION

3rd Floor Eldon House,
2 Eldon Street,
London EC2M 7LS
Tel: 020 7422 7800
Website: www.mlmgroupltd.com

CLIENT: CASTLEFIELD INTERNATIONAL LTD

PROJECT: LAND AT TEVERSHAM ROAD (FULBOURN)

DRAWING TITLE: NEW SITE WIDE EXTERNAL LIGHTING LUX LEVELS

SCALE	1:500 @A0	DRAWN/DESIGN	PG/AC	NUM REF	7151809	REVISION	P03
PROJECT	7151809-MLM-ZZ-GF-DR-E	ORIGINATOR	SYSTEM	LOCATION	TYPE	SCALE	NUMBER